

9-15-87

To: 1 070422
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,259.0000
SW SW NE, SEC. 4, T. 21 S, R. 18 W
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5290

Lease Name Dirks Well # 1

Operator: Hinkle Oil Company
Name & Address 1016 Union Center Building
Wichita, KS 67202

County Pawnee 133.25

Well Total Depth 4100 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:45 a.m. Day: 15 Month: 9 Year: 1987

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4095' PBD 4077' Perfs at 4034-38'

1st plug sand back to 3980' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 500 lbs. hulls and 120 sx ATL cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 15 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3980' and dumped 5 sx cement on top of sand
through bailer, 9-22-87

2nd plug pumped 500 lbs. hulls and 120 sx ATL cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 1987

Maximum pressure 1400 psi and shut in 1100 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used ATL cement by Allied. Recovered 1800' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

~~did not observe~~ observe this plugging.

INVOICED

DATE 9-24-87

Signed Dan Goodrow
(TECHNICIAN)

WV. NO. 18222