

1030214

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,130 .0000
E/2 SE NE, SEC. 21, T 21 S, R 16 *(W)*

TECHNICIAN'S PLUGGING REPORT

1980 feet from ~~N~~ section line
330 feet from ~~W~~E section line

Operator License # 5418

Lease Name Boyd Well # 1-21

Operator: Allen Drilling Company

County Pawnee

Name & Address P. O. Box 1389

Well Total Depth 3200 ^{104.00} feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 983

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418

Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 8:00 pm Day: 25 Month: June Year: 19 84

Plugging proposal received from Don Kerns

(company name) Allen Drilling (phone) 316-793-3582

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1020' with 50 sx cement

2nd plug at 390' with 25 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

Plug water well with 5 sx cement

Plugging Proposal Received by _____
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:30 pm Day: 25 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement, 2nd plug at 390' with 25

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, Plug water well

with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc

JUL 06 1984 7-6-84

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(operator/gie not) observe this plugging.

Signed Steve Belmont
(TECHNICIAN)

DATE 7-13-84

INV. NO. 2482

6-25 JUL 17 1984