

1 090049

2-16

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,339

NW NW NE, SEC. 12, T 21 S, R 26 W/K

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4868

Lease Name Clifton Well # 1

Operator: Asher Associates Inc.

County Hodgeman 144.30

Name & Address 7340 E. Caley Ave., #310

Well Total Depth 4440 feet

Englewood, CO 80111

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 490

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104

Address P.O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 7 p.m. Day: 16 Month: 2 Year: 19 90

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Company, Inc. (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1588-1620'

1st plug at 1620' with 50 sx cement, 2nd plug at 810' with 80 sx cement,

3rd plug at 520' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Mike Wilson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:30 p.m. Day: 16 Month: 2 Year: 1990

ACTUAL PLUGGING REPORT 1st plug at 1620' with 50 sx cement,

2nd plug at 810' with 80 sx cement,

3rd plug at 520' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)

INVOICED FEB 22 1990

observe this plugging.

DATE 2-26-90

Signed Michael R Wilson (TECHNICIAN)

INV. NO. 27560

EFFECTIVE DATE: EFFECTIVE DATE: NOTICE OF INTENTION TO DRILL 15.083.21339.0000
Must be approved by the K.C.C. five (5) days prior to commencing well

ALL BLANKS MUST BE FILLED

Expected Spud Date January 31, 1990
month day year

NW NW NE Sec 12 Twp 21 S Rg 26 East West

OPERATOR: License # 4868
Name: Asher Associates Inc.
Address: 7340 E. Caley Ave. #310
City/State/Zip: Englewood, CO 80111
Contact Person: Harold Patton
Phone: 303.770-4100

4950 feet from South line of Section
2310 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5104
Name: Blue Goose Drilling Co., Inc.

County: Hodgeman
Lease Name: Clifton Well #: 1
Field Name: unknown
Is this a Prorated Field? yes X no
Target Formation(s): Mississippi
Nearest lease or unit boundary: 330
* Ground Surface Elevation: unknown 2407 feet MSL

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary *
... OAWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes *

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 150 200
Depth to bottom of usable water: 440
Surface Pipe by Alternate: X 1
Length of Surface Pipe Planned to be set: 460
Length of Conductor pipe required: NA
Projected Total Depth: 4450
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
... well X farm pond other

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth:

DWR Permit #:
Will Cores Be Taken? yes X no
If yes, proposed zone:

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

* WAS * WAS 750
UNKNOWN * WAS 790

* WAS 780
460' Alt. I Req.

EXP. 8/2/90 AFFIDAVIT

PUSHER Martin Miller

TD 4440 FORMATION MISS

SURFACE PIPE 8 5/8 @ 490

ANHYDRITE 1588-1620 ELEVATION 2417

STARTING TIME & DATE 7:00p 2-16-90

COMPLETION TIME & DATE 9:30p 2-16-90

1st PLUG @ 1680 FT. W/ 50 SX

2nd PLUG @ 810 FT. W/ 80 SX

3rd PLUG @ 520 FT. W/ 40 SX

4th PLUG @ 40 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 15 SX

MOUSE HOLE CIRCULATED W/ SX

WATER WELL PLUGGED W/ SX


CEMENT COMPANY Allied

TECHNICIAN Mike Wilton

TYPE OF CEMENT 60/40 cement

w/6 bags

8-15-90



REMEMBER TO:
- Pit Application (form CDP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- file acreage attribution plat according to field proration orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water

Mail to: Conservation Division, 200 Colorado Derby Building, 202 W. First St., Wichita, Kansas 67202-1286.

CONSERVATION DIVISION
Wichita, Kansas

FEB 22 1990