

1 060045

(1-2)

15.083.21357.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,357

N/2 NE NE, SEC. 19, T 21 S, R 26 W XX

4950 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6574

Lease Name Stacy Well # 1

Operator: Bird Energy, Inc.

County Hodgeman 148.20

Name & Address P.O. Box 1612

Well Total Depth 4560 feet

Dodge City, KS 67801

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company License Number 5929

Address 310 W. Central, #117, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 21 Month: 11 Year: 19 90

Plugging proposal received from Jay Snider

(company name) Duke Drilling Company (phone) 316-267-1331

Elevation 2504'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1713-42'

1st plug at 1755' with 50 sx cement, 2nd plug at 875' with 50 sx cement,

3rd plug at 290' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12 p.m. Day: 21 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 1755' with 50 sx cement,

2nd plug at 875' with 50 sx cement,

3rd plug at 290' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1990 11-27-90

Remarks: Used 60/40 Pozmix 6% gel by Allied.

INVOICED

If additional description is necessary, use BACK of this form.

I (did / did not) observe this plugging.

DATE 12-10-90

Signed *Case Morris* (TECHNICIAN)

INV. NO. 30147

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 5 1990 N/2 NE NE Sec 19 Twp 21 S, Rg 26 East West

OPERATOR: License # 6574
Name: Bird Energy, Inc
Address: Box 1612
City/State/Zip: Dodge City, Ks 67801
Contact Person: Louis S. Bird
Phone: (316) 227 6041

4950 feet from South line of Section
660 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5929
Name: Duke Drilling Co., Inc

County: Hodgeman
Lease Name: Stacy Well #: 1
Field Name: Wild Cat
Is this a Prorated Field? yes X no
Target Formation(s): Miss.
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2495 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 350'
Depth to bottom of usable water: 900'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 240'
Length of Conductor pipe required: none
Projected Total Depth: 4600'
Formation at Total Depth: Miss.
Water Source for Drilling Operations: well X farm pond other

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

DWR Permit #:
Will Cores Be Taken?: yes X no
If yes, proposed zone:
240' Alt. II Req.

Exp. 4/29/91

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Jay Sneider
SPUD DATE 11-14-90 INIT. SLD
LENGTH SURFACE PLANNED 250' ±
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 260 CONDUCTOR
ANHYDRITE T- 1713 B- 1742 ELEVATION 2504
TD 4560 FORMATION Miss
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 1755 Ft. W/ 50 SX
1/2 Base Anhy. @ 875 Ft. W/ 50 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 290 Ft. W/ 50 SX
40 Plug @ 40 Ft. W/ 10 SX
RAT HOLES @ W/ 5 SX MOUSE HOLE W/ SX
WATER WEIGH 5 SX (Irr. Well Pond Hauling)
TECHNICIAN C/A DATE 11-19-90
TYPE OF CEMENT 60/40 67D
STARTING TIME 10:00 (AM/PM) DATE 11-21-90
COMPLETION TIME 12:00 (AM/PM) DATE 11-21-90
CEMENT COMPANY Allied
Total No 7173