

1 070728

9-29

173 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-21,329.0000

NW SE SE, SEC. 36, T 21 S, R 26 W/X

990 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4569

Lease Name Cline Well # 1

Operator: Jay Boy Oil, Inc.

County Hodgeman 146.25

Name & Address 100 North Broadway, Suite 535

Well Total Depth 4500 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 472

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 12 a.m. Day: 29 Month: 9 Year: 19 89

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2409' Anhydrite 1594-1631'

1st plug at 1650' with 50 sx cement, 2nd plug at 700' with 65 sx cement,

3rd plug at 490' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:30 a.m. Day: 29 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement,

2nd plug at 700' with 65 sx cement,

3rd plug at 490' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

DEC 04 1989

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this Form)

INVOICED

(If not observed) observe this plugging.

DATE 10-9-89

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 26050

9-29 DEC 15 1989

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date August 27, 1989  
month day year

NW SE SE Sec 36 Twp 21 S, Rg 26 East  
XX West

OPERATOR: License # 4569  
Name: Jay Boy Oil, Inc.  
Address: 100 No. Broadway #535  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Jay Ablah  
Phone: (316) 264-3700

990 feet from South line of Section  
990 feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # 6033  
Name: Murfin Drilling Company  
250 N. Water, Suite 300

County: Hodgeman  
Lease Name: Cline Well #: 1  
Field Name: UNKNOWN  
Is this a Prorated Field? yes XX no  
Target Formation(s): Mississippian  
Nearest lease or unit boundary: 990'  
Ground Surface Elevation: 2409 feet MSL  
Domestic well within 330 feet: yes XX no  
Municipal well within one mile: yes XX no  
Depth to bottom of fresh water: 380'  
Depth to bottom of usable water: 420'  
Surface Pipe by Alternate: X. 1 350' 450'  
Length of Surface Pipe Planned to be set: none  
Length of Conductor pipe required: none  
Projected Total Depth: 4600'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
... well ... farm pond XX other

Well Drilled For: Well Class: Type Equipment:  
XX Oil ... Inj ... Infield XX Mud Rotary  
... Gas ... Storage XX Pool Ext. ... Air Rotary  
... OWMO ... Disposal ... Wildcat ... Cable  
... Seismic; ... # of Holes

If OWMO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? ... yes XX no  
If yes, total depth location: \_\_\_\_\_

DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken?: ... yes XX no  
If yes, proposed zone: \_\_\_\_\_

450' Alt. I Req.

AFFIDAVIT

PUSHER Rod Farr  
TD 4500 FORMATION Miss  
SURFACE PIPE 8 5/8" @ 472'  
ANHYDRITE 1594' ELEVATION 2409'  
STARTING TIME & DATE \_\_\_\_\_  
COMPLETION TIME & DATE 2:30am 9-29-89  
1st PLUG @ 1650 FT. W/ 50 SX  
2nd PLUG @ 700 FT. W/ 65 SX  
3rd PLUG @ 490 FT. W/ 40 SX  
4th PLUG @ 40 FT. W/ 10 SX  
RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ \_\_\_\_\_ SX  
WATER WELL PLUGGED W/ \_\_\_\_\_ SX  
CEMENT COMPANY Allied  
TECHNICIAN Allied  
TYPE OF CEMENT 60/40 67

SOLD 9-20-89  
450-85784  
MD WW

RECEIVED  
STATE COMMISSION  
OCT 04 1989

4950	1986
4620	1650
4290	1320
3960	990
3630	660
3300	330
2970	
2640	
2310	
1980	
1650	
1320	
990	
660	
330	

6 months of effective date.)  
Spud date: \_\_\_\_\_ Agent: \_\_\_\_\_

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
  - File Completion Form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.

MD