

15.185.10652.0000

To: 1 120695
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-1

API NUMBER 15- Drill Completion Date 11/7/49 17

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337
Operator: Nadel & Gussman
Name &
Address 3200 First National Tower
Tulsa, OK 74103

NE SW SE, SEC. 25, T. 21 S, R. 13 W/E
990 feet from S section line
1650 feet from E section line
Lease Name Fischer Well # B-3
County Stafford
Well Total Depth 3630 117.97 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 8:30 a.m. Day: 1 Month: 4 Year: 19 92

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3627' w/125 sx cement, Open hole
1st plug sand 5 1/2" casing back to 3575' and dump 5 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 10 sx gel and 250 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 1 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3575' and dumped 5 sx cement
on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 50 sx cement with 50 lbs. hulls and 10 sx
gel with 50 lbs. hulls, 100 lbs. hulls, and 200 sx cement.
Pumping pressure 0-200 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 300' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
I hereby acknowledge and agree to observe this plugging.

DATE 4-28-92
INV. NO. 35085

Signed Steve Durrant
(TECHNICIAN)