

10-14-87

1 120033

No: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA 15.185.10656.0000  
NW NW SE, SEC. 25, T 21 S, R 13 W/EX  
2310 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337  
Operator: Nadel and Gussman  
Name & Address: 3232 First National Tower  
Tulsa, OK 74103

Lease Name Fischer Well # B-7  
County Stafford 117.65  
Well Total Depth 3620 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing Company License Number NA  
Address Box 31, Russell, KS 67665

Company to plug at: Hour: 11:30 a.m. Day: 14 Month: 10 Year: 19 87

Plugging proposal received from Frank Neff  
(company name) Nadel and Gussman (phone) 918-583-3333

were: 5 1/2" at 3618' Perfs at 3442-70'  
1st plug pump 200 lbs. hulls and 300 sx ATL cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 14 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 150 sx lite cement with 200 lbs. hulls into 5 1/2" casing,  
2nd plug pumped 150 sx lite cement with 100 lbs. hulls into annulus 5 1/2" X 8 5/8".

5 1/2" casing - pumping pressure 250 psi and shut in 0 psi on vac. closed valve. 10-21-87  
8 5/8" - pumping pressure 450-500 psi and shut in 200 psi. OCT 21 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used lite cement by Allied. No recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 10-22-87

Signed Duane Rankin  
(TECHNICIAN)

INV. NO. 18620