

To: 1 040625 2-21
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15.185.10643.0000
API NUMBER 15- Drill Completion 1/30/49
SE SE NW, SEC. 25, T. 21 S, R. 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337
Operator: Nadel and Gussman
Name &
Address 3200 First National Tower
Tulsa, OK 74103

2970 feet from S section line
2970 feet from E section line
Lease Name Fanshier Well # 1
County Stafford 117.71
Well Total Depth 3622 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 21 Month: 2 Year: 19 92

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3620' w/100 sx cement, Open hole at 3620-3622'
1st plug sand back to 3580' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
2-26-92
FEB 26 1992

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 21 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 200 lbs. hulls, and 125 sx cement. Maximum pressure 200 psi and shut in 75 psi.
(Pumped 300 lbs. hulls and 2 sx gel, fluid circulated up backside of 8 5/8" surface pipe.)

Had hole in surface pipe. Ragged off hole in surface pipe by pumping gunny sacks down 8 5/8",
completed plugging.)

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1207.55' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 3-5-92

INV. NO. 34676

Signed Stephen J. Peyer (TECHNICIAN)