

1080412

15.185.10646.0000

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 10-16-51

SW SE NW, SEC. 25, T 21 S, R 13 W E

2970 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name Franshier Well # 4

Operator: Nadel and Gussman

County Stafford 117.88

Name & Address 3232 First National Tower

Well Total Depth 3627 feet

Tulsa, OK 74103

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Nadel and Gussman License Number 5337

Address 3232 First National Tower, Tulsa, OK 74103

Company to plug at: Hour: 9:00 am Day: 21 Month: August Year: 1985

Plugging proposal received from Frank Neff

(company name) Nadel and Gussman (phone) 918-583-3333

were: 5 1/2" at 3625 1/2', Perfs at 3456-3465 and 3488-3494'

Pump 1 sack hulls, 50 sx cement, 7 sx gel, and 100 sx cement down 5 1/2"

Pump 125 sx cement down 8 5/8"

Plugging Proposal Received by J. A. Neff (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 am Day: 21 Month: August Year: 1985

ACTUAL PLUGGING REPORT Pumped 1 sack hulls, 50 sx cement, 7 sx gel and 100 sx cement

down 5 1/2" - Maximum pressure 400 psi and shut in 200 psi

Pumped 125 sx cement down 8 5/8" - Maximum pressure 400 psi and shut in 250 psi

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

AUG 28 1985

DATE

INV. NO. 9830

RECEIVED

AUG 28 1985

Signed

J. A. Neff (TECHNICIAN)