

3-15 15.185.10662.0000 200 R

To: 1 120543  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 9/15/51  
NE NW SW, SEC. 25, T 21 S, R 13 W/E  
2310 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5337  
Operator: Nadel and Gussman  
Name & Address 3200 First National Tower  
Tulsa, OK 74103

Lease Name Fischer Well # D-4  
County Stafford 118.04  
Well Total Depth 3632 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8 a.m. Day: 15 Month: 3 Year: 19 91

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3630' w/125 sx cement, PRTD 3300', Perfs at 3456-66', Casing parted at 360'  
1st plug set CIBP at 3300' with 2 sx cement on top,  
2nd plug run tubing to 750' and circulate cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 15 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3300' and dumped 2 sx cement on top with bailer,  
2nd plug ran tubing in 8 5/8" to 750' and circulated cement with 355 sx cement,  
3rd plug pulled tubing and filled hole with 40 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 20 1991

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 360' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED (stamped) observe this plugging.

DATE 4-2-91  
INV. NO. 31289

Signed [Signature] (TECHNICIAN)