

1080411

15.185.10663.0000

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 1-30-52

SW NE SW, SEC. 25, T 21 S, R 13 W/E

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name Fischer Well # D-6

Operator: Nadel and Gussman

County Stafford 117.52

Name & Address 3232 First National Tower

Well Total Depth 3616 feet

Tulsa, OK 74103

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Nadel and Gussman License Number 5337

Address 3232 First National Tower, Tulsa, OK 74103

Company to plug at: Hour: 11:00 am Day: 21 Month: August Year: 1985

Plugging proposal received from Frank Neff

(company name) Nadel and Gussman (phone) 918-583-3333

were: 5 1/2" at 3613' Perfs at 3444-3456'

Pump 200 sx cement down 5 1/2" casing

Pump 125 sx cement down back side

Plugging Proposal Received by J. H. Neff (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:15 pm Day: 21 Month: August Year: 1985

ACTUAL PLUGGING REPORT Pumped 200 sx cement down 5 1/2" casing filling pipe

Pumped 125 sx cement down back side. Maximum pressure 400 psi and shut in 200 psi

Remarks: No Recovery. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 28 1985

INV. NO. 9829

RECEIVED STATE CORPORATION COMMISSION

AUG 28 1985

Signed J. H. Neff (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas