

To: 1 120696
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15.185.10649.0000
4-1 API NUMBER 15-Drill Completion Date 10/1/51
NE SE SW, SEC. 25, T. 21 S, R. 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Operator: Nadel and Gussman
Name & Address 3200 First National Tower
Tulsa, OK 74103

Lease Name Fischer Well # A-3
County Stafford
Well Total Depth 3615 117.48 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 11:30 a.m. Day: 1 Month: 4 Year: 19 92

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3614' w/150 sx cement, Perfs at 3163-67' and open hole

1st plug sand 5 1/2" casing back to 3310' and dump 5 sx cement on top of sand through bailer;
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 1 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3310' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2350' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-28-92
INV. NO. 35084

Signed *Steve Durrant*
(TECHNICIAN)