

1 120799

6-15

Docket

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-15,785 15.185.10650.0001

SW SW SE, SEC. 25, T 21 S, R 13 W/E
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name Fischer Well # B-1

Operator: Nadel & Gussman

County Stafford

Name & Address 3200 First National Tower

Well Total Depth 3652 118.69 feet

Tulsa, OK 74103

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 2:30 p.m. Day: 15 Month: 6 Year: 19 93

Plugging proposal received from Frank Neff

(company name) Nadel & Gussman (phone) 316-793-7820

logs: 5 1/2" at 3629' w/125 sx cement, PBTD 3510', Perfs at 3381-99, 3462-3500'

1st plug sand back to 3330' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 300 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 15 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3330' and dumped 5 sx cement on top of sand through bailer,

RECEIVED STATE CORPORATION COMMISSION

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls and 300 sx cement.

JUN 18 1993

Pumping pressure 100 psi and shut in 50 psi.

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 350' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-30-93 (and / month / year) observe this plugging.

INV. NO. 38025

Signed Duane Rankin (TECHNICIAN)