

1 120800

6-15

15.185.10658.0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-15,785

NE NW SE, SEC. 25, T 21 S, R 13 W&X

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337

Lease Name Fischer Well # B-9

Operator: Nadel & Gussman

County Stafford

Name & Address

Well Total Depth 3694 120.05 feet

3200 First National Tower

Conductor Pipe: Size _____ feet

Tulsa, OK 74103

Surface Casing: Size 8 5/8 feet 127

Abandoned Oil Well _____ Gas Well _____ Input Well X SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 12:30 p.m. Day: 15 Month: 6 Year: 19 93

Plugging proposal received from Frank Neff

(company name) Nadel & Gussman (phone) 316-793-7820

Work: 5 1/2" at 3620' w/150 sx cement, PBSD 3584', Perfs at 3372-76, 3437-3505'

1st plug sand 5 1/2" casing back to 3320' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls and 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 15 Month: 6 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug sanded back 5 1/2" casing to 3320' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

200 lbs. hulls, and 125 sx cement.

Pumping pressure 0-500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2350' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / XXXXXX) observe this plugging.

DATE 6-29-93

INV. NO. 38024

Signed Steve Durrant (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION JUN 18 1993 CONSERVATION DIVISION Wichita, Kansas