

To: 1 120804  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-28  
RECEIVED  
7-1-93  
JUL 07 1993  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KS

API NUMBER 15- 185-20,618-0000  
SE NE NW, SEC. 22, T 21 S, R 13 W/EX  
4290 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6588  
Operator: Woodman-Iannitti Oil Company  
Name:  
Address P.O. Box 308  
Great Bend, KS 67530

Lease Name Hoffman Well # 2  
County Stafford  
Well Total Depth 3660 118.95 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 28 Month: 6 Year: 1993

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 816-938-2943

were: 5 1/2" at 3647' w/100 sx cement

1st plug sand back to 3600' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 28 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.

INVOICED (If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 7-8-93 Signed Duane Rankin (TECHNICIAN)

INV. NO. 38067