

1 080596

FEB 5 1987

15.185.20384.0000

API NUMBER 15- N/A

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SW, SEC. 22, T 21 S, R 13 W/E
2310 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9069

Lease Name Sipes Well # A-3

Operator: General Oil Company
Name & Address: 1540 North Broadway, #203
Wichita, KS 67214

County: Stafford 120.09

Well Total Depth 3695 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Company, Inc. License Number N/A

Address Box 31, Russell, KS 67665

Company to plug at: Hour: 8 a.m. Day: 5 Month: 2 Year: 1987

Plugging proposal received from Bob Moorehead

(company name) Allied Cementing Company (phone) 913-483-2627

were: 4 1/2" at 3693' PBTB 3683' Perfs at 3678-87'

1st plug spot 35 sx cement and 75 lbs. hulls at 3441' (plug through tubing),

2nd plug spot 10 sx gel at 2475', 3rd plug spot 100 sx cement and 50 lbs. hulls at 900',

4th plug spot 50 sx cement at 546' with 100 lbs hulls, 5th plug spot 50 sx cement at 386'

with 100 lbs. hulls, and 6th plug spot 80 sx cement at 225'.

Plugging Proposal Received by J.H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 5 Month: 2 Year: 1987

ACTUAL PLUGGING REPORT 1st plug spotted 35 sx 60/40 Pozmix cement with 75 lbs. hulls at

3441', plug through tubing on all plugs

2nd plug spotted 10 sx gel at 2475', 3rd plug spotted 100 sx common cement and 50 lbs.

hulls at 900', 4th plug spotted 50 sx cement at 546' with 100 lbs. hulls,

5th plug spotted 50 sx cement at 386' with 100 lbs hulls, 6th plug spotted 80 sx cement

at 225'. Cement circulated. 2-12-87

Remarks: Used 60/40 Pozmix and common cement by Allied. Recovered 288' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed J.H. Metz (TECHNICIAN) FEB 12 1987 CONSERVATION DIVISION

DATE 2-16-87

INV. NO. 16124