

To: 1 080439
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-20,583.0000
SW NW NE, SEC. 22, T 21 S, R 13 W/2X
4290 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588
Operator: Woodman-Iannitti Oil Company
Name & Address P. O. Box 308
Great Bend, KS 67530

Lease Name Schulz Well # 3
County Stafford
Well Total Depth 3672 119.34 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 295

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P. O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2:00 pm Day: 25 Month: October Year: 19 85

Plugging proposal received from Deacon Pulley

(company name) Rockhold (phone) 316-792-2506

were: 5 1/2" at 3658' Open Hole

1st plug sand back to 3600' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 pm Day: 25 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 800 psi and shut in 400 psi

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan. Recovered 2500' 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE NOV 4 1985
INV. NO. 10898

observe this plugging.
RECEIVED
STATE CORPORATION COMMISSION
Signed J. A. Med
(TECHNICIAN)

NOV 1 1985
11-1-85