

15.185.01725.0000

1052288

TO: STATE CORPORATION COMMISSION

9-1

API NUMBER 15-185-01725 drilled in 1943
SW/4 SEC. 22, T 21 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME KRONE WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 6170 WELL TOTAL DEPTH 3677 119.51 FEET

OPERATOR: GLOBE OPERATING, INC PRODUCTION CSG: SIZE 5 1/2 " FEET 3669'

NAME AND PO BOX 12 SURFACE CASING: SIZE 8 5/8" FEET 380'

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 3:00 PM DAY: 01 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MANNY BOATRIGHT

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2943

WERE: PERFS AT 3370 TO 3510

1ST PLUG SAND TO 3320' & 5 SX CEMENT

2ND PLUG AT 750' WITH 10 SX GEL & 50 SX CEMENT

3RD PLUG AT 400' WITH 50 SX CEMENT

4TH PLUG AT 40' WITH 10 SX CEMENT

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:50 PM DAY: 01 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 3320' & 5 SX CEMENT

2ND PLUG AT 750' WITH 10 SX GEL & 50 SX CEMENT

3RD PLUG AT 400' WITH 50 SX CEMENT

4TH PLUG AT 40' WITH 10 SX CEMENT

REMARKS: 60/40 POZ MIX 6% GEL BY ALLIED. 1800' OF 5 1/2" CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

DATE 9-10-98

INV. NO. 51294

RECEIVED
AS CORP.
11/11

9-8-98