

To: 1 121027 4-19-95  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-20,294-6000

NW NW SE, SEC. 22, T 21 S, R 13 W/EX

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30742

Lease Name Schulz Well # 1

Operator: Palomino Petroleum, Inc.

County Stafford

Name & Address 4924 SE 84th St.

Well Total Depth 3665 119.11 feet

Newton, KS 67114-8827

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 11 a.m. Day: 19 Month: 4 Year: 1995

Plugging proposal received from Joe Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 5 1/2" at 3663', Open hole, Casing ripped at 715', Anhydrite 710'

1st plug sand back to 50' above perfs and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 19 Month: 4 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3610' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, and 150 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 540' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED (XXXXXX) observe this plugging.

DATE 4-26-95

Signed Duan Randon (TECHNICIAN)

INV. NO. 42704

4-25-95  
RECEIVED  
STATE CORPORATION COMMISSION  
APR 25 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS