

To: 1121026 4-19  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-22,820

N/2 N/2 S/2, SEC. 22, T 21 S, R 13 W/EK

TECHNICIAN'S PLUGGING REPORT

Operator License # 30742

Operator: Palomino Petroleum, Inc.

Name & Address 4924 SE 84th St.

Newton, KS 67114-8827

2310 feet from S section line

2640 feet from E section line

Lease Name Schulz-Sipes GWell # 1

County Stafford

Well Total Depth 3720 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 372

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9 a.m. Day: 19 Month: 4 Year: 19 95

Plugging proposal received from Joe Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

were: 5 1/2" at 3717' w/125 sx cement, Open hole

1st plug sand back to 50' above perfs and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:40 a.m. Day: 19 Month: 4 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3660' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Please observe this plugging.

Signed Juan Rankin (TECHNICIAN)

DATE 4-26-95

NOV. NO. 42705

RECEIVED  
STATE CORPORATION COMMISSION  
APR 25 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS