

To: 1 120581  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200, COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5427  
Operator: D.R. Lauck Oil Company, Inc.  
Name & Address: 221 S. Broadway, Suite 400  
Wichita, KS 67202

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D.R. Lauck Oil Company, Inc. License Number 5427  
Address 221 S. Broadway, Suite 400, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 18 Month: 6 Year: 19 91

Plugging proposal received from Melvin Urban  
(company name) D.R. Lauck Oil Company, Inc. (phone) 316-564-2013

were: 5 1/2" at 3634' w/125 sx cement, PBSD 3486', Perfs at 3326-3473', 5 1/2" squeezed at 288'  
w/200 sx cement

1st plug pump in 5 1/2" casing with 3 sx hulls and fill with cement,  
2nd plug check 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour: 11:30 a.m. Day: 18 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped into 5 1/2" casing with 400 lbs. hulls and 350 sx cement.  
No pressure, not on vacuum.

Pumped in 8 5/8" X 5 1/2" annulus to 1500#. No material.  
RECEIVED  
STATE CORPORATION COMMISSION  
JUN 25 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)  
INVOICED  
DATE JUL 22 1991  
INV. NO. 32337  
Signed \_\_\_\_\_ (TECHNICIAN)

6-18 SEP 27 1991  
FORM CP-2/3  
Rev. 01-84

6-18 15.185.00334.0000  
API NUMBER 15- Drill Completion Date 7/31/56  
SE SE SE, SEC. 22, T 21 S, R 13 W/E  
330 feet from S section line  
330 feet from E section line  
Lease Name Schulz "C" Well # 1  
County Stafford 118.23  
Well Total Depth 3638 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 259