

To: 120958  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-24  
API NUMBER 15- 185-20,335.0000  
SW NW SE, SEC. 22, T. 21 S, R. 13 W  
1650 feet from S section 11  
2310 feet from E section 11

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30742

Lease Name Schulz Well # 2  
County Stafford  
Well Total Depth 3693 120.02 ft  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 394

Operator: Palomino Petroleum, Inc.  
Name:  
Address 4924 SE 84th St.  
Newton, KS 67114-8827

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901  
Address P.O. Box 231, Claflin, KS

Company to plug at: Hour: 3 p.m. Day: 24 Month: 8 Year: 19 94

Plugging proposal received from Kevin Strube  
(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

vars: 5 1/2" at 3690' w/100 sx cement, PBTD 3690', Perfs at 3685-87'  
1st plug sand back to 3630' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump in 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,  
release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 4 p.m. Day: 24 Month: 8 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3630' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement. 8-31-94  
Pumping pressure 0-600 psi and shut in 200 psi.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1997' of 5 1/2" casing. AUG 31 1994

INVOICED  
If additional description is necessary, use BACK  
observe this plugging.

DATE SEP 12 1994  
INV. NO. 41194

Signed Duane Rankin  
(TECHNICIAN)