

To: 1 120704
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15.185.10627.0001 217
4-22 API NUMBER 15- Drill Completion Date 7/24/53
SE SE SE, SEC. 19, T. 21 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: OXY USA INC.
Name
Address P.O. Box 26100
Oklahoma City, OK 73126-0100

330 feet from S section line

330 feet from E section line

Lease Name Pundsack U. Well # 104W

County Stafford

Well Total Depth 3757 122.10 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 805

Abandoned Oil Well Gas Well Input Well Terminated Flood SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor OXY USA INC. License Number 5447

Address P.O. Box 26100, Oklahoma City, OK 73126-0100

Company to plug at: Hour: 8:30 a.m. Day: 22 Month: 4 Year: 1992

Plugging proposal received from Don Herman

(company name) OXY (phone) 316-532-2002

logs: 5 1/2" at 3723' w/200 sx cement, PBTD 3685', Perfs at 3501-72' (5 sets)

1st plug set CIBP at 3000' with 5 sx cement on top with bailer,

2nd plug run tubing to 3500', pump 50 sx cement,

3rd plug perforate at 820', circulate cement to surface.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 22 Month: 4 Year: 1992

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3010' with 5 sx cement on top with bailer,

2nd plug pressured 5 1/2" casing to 300#, perforated 5 1/2" casing at 820' and circulated with

225 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by HOWCO. No casing recovery.
(If additional description is necessary, use BACK of this form)

INVOICED
I (and my employees) observe this plugging.

DATE 5-12-92

INV. NO. 35209

Signed Duane Rankin
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1992
CONSERVATION DIVISION
Wichita, Kansas