

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 30 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Drillers Production Company, Inc.  
 Complete Address: 480 Fourth National Bank Bldg., Wichita, Kansas  
 Lease Name Lorimor "B" Well No. # 1  
 Location C SW NE Sec. 20 Twp. 30 Rge. 20 (E) (W)  
 County Kiowa Total Depth 5296'  
 Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
 Other well as hereafter indicated:       
 Plugging Contractor: Knight Casing Pulling Company  
 Address: Box 405, Chase, Kansas License No. 436  
 Operation Completed: Hour 5:00PM Day 21st Month August Year 1965

The Above well was plugged as follows:

528' of 8 5/8" surface pipe, cemented with 425 sacks. 5296' of 5 1/2" long string, cemented with 200 sacks. Plug back to 5252'. Top perferation 5160'. Bottom of the hole was sanded to 5150', and cemented with 5 sacks. 4244' of 5 1/2" long string was recovered from the hole. Hole was filled with mud to 300', rock bridge from 300' to 290', and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

**INVOICED**

DATE 8/30/65  
INV. NO. 1719-w