

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name DNB Drilling Inc.

Complete Address 515 R.H.Garvey Bldg., Wichita, Ks. 67202

Lease Name Huck "A" (OWWO) Well No. 2

Location NW NW NE Sec. 20 Twp. 30 Rge. 20 (E) (W) X

County Kiowa Total Depth 5272

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 1 Pm. Day 28 Month 4 Year 1980

The above well was plugged as follows:

328' 8 5/8" casing-4 1/2" casing set at 5208' w/100 sax cement. Plug
back to 5173'-Preforated at 5154 to 60'-Allied mixed & pumped 35 sax
common cement in 4 1/2" casing to 5000'-Pull 4515' casing-Allied mixed
& pumped 8 sax hulls-25 sax gel-125 sax 50/50 posmix cement w/4% gel
& 3% cc in 8 5/8" casing to top of casing. Shut in w/250# pressure.

4-30-80

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor
(CONSERVATION DIVISION
Wichita Kansas)

INVOICED
DATE 4-30-80
INV. NO. 20262