

[Signature]
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1975

CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Anadarko Production Co.

Complete Address Box 351 Liberal, KS

Lease Name Gillette A Well No. 7

Location NW/NW Sec. 15 Twp. 30E Rge. 19 (E) (W) W

County Kiowa Total Depth 5189

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pratt Well Service Inc

Address 723 S Minnescah Pratt, KS License No. _____

Operation Completed: Hour 4:00 PM Day 1 Month 7 Year 1975

The above well was plugged as follows:

422 ft 8 5/8 surface cemented with 450 sacks. 5189 ft 4 1/2 long string

cemented with 140 sacks. Top perf. 5094 ft. Pump 30 sacks cement to

4800 ft. Pulled 3770 ft 4 1/2. Pump/50 sacks cement to 450 ft.

Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.

Pumped by Halliburton Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

Signed: *[Signature]*
Well Plugging Supervisor

INVOICED

DATE ~~1563-W~~ 7/3/75

INV. NO. 7/3/75