

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-097-20,827 ✓

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Graham Michael's Corp.

Complete Address 211 N. Broadway Box 247 Wichita, Kansas 67202

Lease Name Robbins Morton Well No. 1-35

Location C-SW-SW Sec. 35 Twp. 30 Rge. 18W (East) (West)

County Kiowa Total Depth 5125'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Lawson Drilling Co. Inc

Address 200 Douglas Alley, Broadway, Douglas 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 5:45 AM Day: 20 Month: December Year: 19 81

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

There is 803' of 8 5/8" surface casing cement circulated with 800 lbs. of cement. The anhydrite is at 1070'. 1st plug at 1000 with 50 lbs of cement. 2nd plug push rubber plug to 780' and grout 35 lbs of cement on top of it. 3rd plug 40' to 0' with 10 lbs of cement. Then pumped 5 lbs of cement in rat hole. The cement used was common with 2 7/8 gal + 3 3/4 cc. The plugging was accomplished by Dowell cementing.

RECEIVED  
STATE CORPORATION COMMISSION  
12-22-81

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul [Signature]  
Conservation Division Agent

DATE 1-20-82

INV. NO. 8970 W

NOTICED