

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued April 6, 1967.

Operator's Full Name Cities Service Oil Company

Complete Address: Box 308, Great Bend, Kansas

Lease Name Koehn "A" Well No. # 1

Location C NE NW Sec. 27 Twp. 30 Rge. 18 (E) (W)W

County Kiowa Total Depth 5165'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 12:30PM Day 16th Month April Year 1967

The Above well was plugged as follows:

452' of 8 5/8" surface pipe, cemented with 275 sacks. 5164' of 4 1/2" long  
string, cemented with 100 sacks. Plug back T.D. 5129'. Top perferation 5063'  
Bottom of the hole was sanded to 5050', and cemented with 3 sacks, through  
the dump bailer. 3045' of 4 1/2" long string was recovered from the hole.  
Bridge plug was pushed in fluid to 325', bridge plug and rock bridge from  
325' to 315'. 4 sacks of cement was mixed in a barrel, and put on plug at  
315', through the dump bailer, and let set over-night. Next day hole was  
bailed dry and 21 sacks of cement was added to the plug. Hole was filled with  
mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the  
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/24/67

INV. NO. 5108-4