

KANSAS

TP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed June 9, 1967.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1967
6-26-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name K & E Drilling, Inc.

Complete Address 719 Union Center Bldg., Wichita, Kansas 67202

Lease Name Kane Unit Well No. # 1-12

Location C NW SE NW Sec. 12 Twp. 30 Rge. 18 (E) (W) W

County Kiowa Total Depth 4905'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor K & E Drilling, Inc.

Address 719 Union Center Bldg., Wichita, Ks. License No.

Operation Completed: Hour 9:30 A.M. Day 24th Month June Year 1967

The above well was plugged as follows:

38' of 13 3/8" surface pipe, cemented with 47 sacks. 374' of 8 5/8"
surface pipe, cement circulated with 253 sacks. Hole was filled with
drilling mud to 365', 1st cementing plug, bridged with 2 sacks of dry
cement and 1/2 sack of hulls on fluid at 365', and cement with 23 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with
1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and cemented
with 9 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/27/67

INV. NO. 5458-W