

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed December 29, 1966

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name K & E Drilling, Inc.
Complete Address: 719 Union Center Bldg., Wichita, Kansas
Lease Name Fincham Unit Well No. # 1
Location C NE SW Sec. 2 Twp. 30 Rge. 18 (E) (W) W
County Kiowa Total Depth 5525'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: K & E Drilling, Inc.
Address: 719 Union Center Bldg., Wichita, Kansas License No.
Operation Completed: Hour 5:00PM Day 25th Month Jan. Year 1967

The Above well was plugged as follows:

463' of 8 5/8" surface pipe, cement circulated with 300 sacks. Hole
was filled with drilling mud to 400', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 400', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/27/67

INV. NO. 4693-W

Signed: Aubrie Elving

Well Plugging Supervisor