

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-20350-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 7-28S-31W
1250 feet from S Section Line, 4030 feet from E Section Line
Lease Name: CORNWELL Well #: 1
County: HASKELL Total Vertical Depth: 2900 feet

Operator License No.: 9412
Op Name: NIGHTENGALE, HENRY (DECEASED)
Address: 694 ROAD SS
SUBLETTE, KS 67877

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2870	0	WITH 150 SX CMT
SURF	8.625	805		WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/13/2017 9:00 AM
Plug Co. License No.: 8438 Plug Co. Name: POST & MASTIN WELL SERVICE, INC.
Proposal Revd. from: JASON AUCTERERH Company: POST & MASTIN WELL SERVICE, I Phone: (620) 276-3442

Proposed Plugging Method: FREE POINT & CUT TBG ABOVE STUCK POINT (2000' OR BELOW). CIRCULATE CMT TO SURFACE WITH APP. 150 SX CMT & 300# HULLS. TOOH WITH TBG. WAIT ON CMT FOR 2 HOURS. TOC & FILL 4 1/2" CASING TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2017 2:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

**WELL HAD A CMT SQUEEZE JOB WITH 330 SX CMT (900' TO 1504') CMT CIRCULATED TO PIT. TBG STUCK IN HOLE. CUT TBG AT 1420'. 1ST PLUG AT 1420' WITH 205 SX CMT WITH 300# HULLS IN FIRST 40 SX CMT. CHECK BACKSIDE WITH 10 SX CMT TO 500#.

Perfs:

Top	Bot	Thru	Comments
2776	2782		
2745	2760		

INVOICED
DEL 15 2017

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY POST & MASTIN.

Plugged through: TBG

District: 01

Signed Heith Walsh
(TECHNICIAN)

SA