

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-21667-00-00
Spot: NWSENNW Sec/Twnshp/Rge: 28-21S-23W
833 feet from N Section Line, 2299 feet from W Section Line
Lease Name: NORTON Well #: 1-28
County: HODGEMAN Total Vertical Depth: 4665 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR E. UNIT F104
ENGLEWOOD, CO 80112

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|--|
| PC | | 1608 | | CEMENTED WITH 150 SX CMT. 15 SX CMT CIRCULATED TO PIT. |
| PROD | 5.5 | 4662 | 0 | WITH 200 SX CMT |
| SURF | 8.625 | 208 | | WITH 150 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2017 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BRADY PFEIFFER Company: NORSTAR PETROLEUM Phone: (785) 798-5051

Proposed Plugging Method: SQUEEZE PERFS WITH 30 SX CMT WITH HULLS. RTIH TO 1620' WITH 10 SX GEL & 30 SX CMT. PLUG AT 660' WITH CMT TO 0'. CHECKBACKSIDE WITH CMT TO 300 PSI.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/10/2017 11:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG TO 4568' & BROKE CIRCULATION WITH 21 SX GEL, THEN PUMPED 30 SX CMT WITH 100# HULLS. PULLED TBG TO 1620' & PUMPED 30 SX CMT. PULLED TBG TO 648' & CIRCULATED CMT TO SURFACE WITH 65 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 300# WITH 25 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4572 | 4582 | | Cherokee |

INVOICED
DEC 15 2017

Remarks: **COMPLIANCE ISSUE: DENIED TA NEED FL** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
OCT 20 2017
KCC DODGE CITY