

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23299-00-00
Spot: SENWSWNE Sec/Twnshp/Rge: 10-10S-24W
1695 feet from N Section Line, 2200 feet from E Section Line
Lease Name: PFEIFER Well #: 1-10
County: GRAHAM Total Vertical Depth: 4030 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR E. UNIT F104
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4030		125 SX
SURF	8.625	220		160 SX
T1	2.375	3985		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2017 8:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD YOHOON Company: NORSTAR PETROLEUM, INC. DBA Phone: (785) 425-8999

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 2112' w/382 sx cement.
Perforations: 3982' - 3986'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2017 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3960' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 3015' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2007' and pumped 75 sx cement. Pulled tubing to 1007' and pumped 110 sx cement. Cement circulated. Pulled tubing out. Topped off casing with 10 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 400 psi.

GPS: 39.19976 -099.98566

Perfs:

Top	Bot	Thru	Comments
3982	3986		

INVOICED
DEC 15 2017

Remarks: QES CEMENTING TICKET #54908

Plugged through: TBG

District: 04

Signed _____

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

NOV 20 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

OCT 26 2017