

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20074-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 24-16S-28W
339 feet from S Section Line, 2278 feet from E Section Line
Lease Name: SCHAEFER Well #: 1
County: LANE Total Vertical Depth: 4703 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4702	0	WITH 100 SX CMT
SURF	8.625	310		WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2017 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: FRITZLER TRUCKING Phone: (620) 546-4752

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. PERFORATE AT 2200' & SPOT 70 SX CMT, HALF WITH HULLS & HALF WITHOUT. PUT HOT 50 SX CMT PLUG AT 1600'. IF HOLD PRESSURE PERFORATE AT 1300' & PUMP 80 SX CMT OVER CASING VOLUME THEN 150 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 10/31/2017 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

10/25/17: RAN TBG TO 4483' & SPOT 50 SX CMT & 200# HULLS. SHUT DOWN FOR WIND. 10/30/17: PERFORATE AT 2200'. RAN TBG TO 2200' & SPOT 70 SX CMT (35 SX CMT WITH 100# HULLS & 35 SX CMT WITHOUT HULLS). SDON. 10/31/17: RAN TBG TO 1600' & SPOT 50 SX COMMON CMT WITH 3% CC. WAIT 1 1/2 HOURS. PRESSURE CASING TO 500#. HELD. RUN & TAGGED CMT AT 1320'. PERFORATED AT 1300' & PUMPED 210 SX CMT. PRESSURED TO 400# & HELD. TIED ONTO BACKSIDE & PUMPED 100 SX CMT. PRESSURED TO 400# & HELD.

Perfs:

Top	Bot	Thru	Comments
4514	4524		

INVOICED

Remarks: USEWD 60/40 POZMIX & COMMON CMT W/3% CC BY SWIFT SERVICES.

DEC 15 2017

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
NOV - 3 2017
KCC DODGE CITY