

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-20794-00-00  
Spot: NESWNWSW Sec/Twnshp/Rge: 20-31S-11W  
1847 feet from S Section Line, 4742 feet from E Section Line  
Lease Name: WATKINS Well #: 1  
County: BARBER Total Vertical Depth: 3645 feet

Operator License No.: 31142  
Op Name: PETROLEUM PROPERTY SERVICES, IN  
Address: 125 N MARKET SUITE 1251  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3576		WITH 2 SX CMT
PROD	4.5	3644	2308	WITH 100 SX CMT
SURF	8.625	210		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/03/2017 10:15 AM  
Plug Co. License No.: 34484 Plug Co. Name: FOSSIL DRILLING, INC.  
Proposal Revd. from: KELLY SCHMEIDLER Company: PETROLEUM PROPERTY SERVICE Phone: (620) 546-4752

Proposed Plugging Method: CIBP @ 3575' WITH 2 SX CMT. LOAD HOLE & TEST CASING. PLUG AT 620' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/03/2017 11:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3576' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 634' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 248' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3616	3622		

INVOICED  
DEC 15 2017

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED  
OCT 11 2017  
KCC DODGE CITY

KMS