

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-20522-00-00
Spot: S2NWSENE Sec/Twunshp/Rge: 17-28S-13W
3382 feet from S Section Line, 912 feet from E Section Line
Lease Name: SMITH C Well #: 1
County: PRATT Total Vertical Depth: 3237 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | 4.5 | 2880 | | WITH 2 SX CMT |
| COND | 10.75 | 233 | | WITH 200 SX CMT |
| PROD | 4.5 | 3222 | 0 | WITH 100 SX CMT |
| SURF | 8.625 | 906 | | WITH 100 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/01/2017 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: KENNY GATES Company: PRATT WELL SERVICE. Phone: (620) 672-2531

Proposed Plugging Method: SET CIBP @ 3125' & 2 SX CMT. PERFORATE 4 1/2" CASING AT 800'. PUMP DOWN 4 1/2" CASING WITH CMT FILLING 4 1/2" AND 4 1/2" X 8 5/8" ANNULUS TO SURFACE WITH CMT. CHECK 8 5/8" X 10 3/4" ANNULUS WITH CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2017 2:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

****STACKED OUT AT 2950**** SET CIBP @ 2880' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PUMPED DOWN 8 5/8" X 10 3/4" ANNULUS WITH 30 SX CMT. PERFORATE 4 1/2" CASING AT 800'. PUMPED DOWN 4 1/2" CASING WITH 250 SX CMT CIRCULATING CMT TO SURFACE INSIDE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3172 | 3176 | CSG | |
| 3158 | 3160 | CSG | |


INVOICED
DEC 15 7/07

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED
NOV - 3 2017
KCC DODGE CITY