

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-20948-00-01
Spot: SWSW Sec/Twnshp/Rge: 33-34S-30W
618 feet from S Section Line, 4507 feet from E Section Line
Lease Name: JESSIE S Well #: 1
County: MEADE Total Vertical Depth: 6500 feet

Operator License No.: 5225
Op Name: QUINQUE OPERATING COMPANY
Address: 908 NW 71ST ST
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4310		
CIBP		5090		WITH 2 SX CMT
CIBP		5400		
CIBP		6250		
COND	20	40		
PROD	5.5	5862	2986	WITH 270 SX CMT
SURF	8.625	1519		WITH 550 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/01/2017 11:00 AM
Plug Co. License No.: 34199 Plug Co. Name: RAWHIDE WELL SERVICE, LLC
Proposal Rcvd. from: JAREN HITCH Company: RAWHIDE WELL SERVICE Phone: (405) 840-9876

Proposed Plugging Method: PULL EXISTING RETRIEVABLE BRIDGE PLUG AT 4310'. SET CIBP @ 5090' WITH 2 SX CMT. LOAD HOLE WITH MUD. PLUG PERFS AT 4243' WITH 25 SX CMT. PLUG AT 1560' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/03/2017 10:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

11/1/17: PULL RETRIEVABLE BRIDGE PLUG AT 4310'. SET CIBP @ 5090' WITH 2 SX CMT. LOAD HOLE WITH MUD. PLUG PERFS AT 4243' WITH 25 SX CMT. CUT CASING AT 3580'. COULD NOT PULL. CUT & PULL CASING AT 2986'. 11/2/17: FINISH PULLING CASING, RUN TBG TO 1573' & PUMP 50 SX CMT BUT HAD NO CIRCULATION. ESTIMATED FLUID AT 90'. TRIED TO LOAD HOLE WITH NO LUCK. SHUT DOWN 11/3/17: RAN TBG TO 1573'. DID NOT TAG CMT. PUMP 50 SX CMT WITH GOOD CIRCULATION. PULL TBG TO 566' & PUMP 50 SX CMT. PULL TBG TO 60'. CIRCULATED TO SURFACE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6275	6282		
5965	6076		
5140	5142		
4335	4342		
4288	4292		

INVOICED
DEC 15 2017

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
NOV - 8 2017
KCC DODGE CITY

Signed

[Signature]
SA (TECHNICIAN)