

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23985-00-00
Spot: SWSWNESW Sec/Twnshp/Rge: 30-28S-8E
1467 feet from S Section Line, 9302 feet from E Section Line
Lease Name: FOUR J, INC. Well #: 1
County: BUTLER Total Vertical Depth: 3176 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3172		150 SX
SURF	8.625	229		130 SX
T1	2.375	3169		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALAN NATION Company: RANGE OIL CO Phone: (620) 222-4304

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 10/19/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3150', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. PERFORATED SQUEEZE HOLES @ 275'-276' (4 HOLES). RIH WITH TUBING @ 260', QWS MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING. SWEDGED INTO 5 1/2" CASING, QWS MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3169	3172	CSG	

INVOICED
DEC 15 2017

Remarks:

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

✓/K