

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22350-00-00
Spot: NESENWNW Sec/Twnshp/Rge: 27-20S-29W
4424 feet from S Section Line, 4289 feet from E Section Line
Lease Name: M & A TRUST Well #: 1
County: LANE Total Vertical Depth: 4819 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4450		WITH 2 SX CMT
DVT	4.5	2195		WITH 455 SX CMT
PROD	4.5	4808	0	WITH 225 SX CMT
SURF	8.625	261		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/19/2017 8:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. RUN TBG TO 2200' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2017 1:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SEST CIBP @ 4450' WITH 2 SX CMT. RUN TBG TO 2210' & PUMPED 190 SX CMT. LOST CIRCULATION. PULLED TBG . TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 300# & HELD. TIED ONTO CASING & PUMPED 90 SX CMT & 200# HULLS. PRESSURED TO 400# & HELD.

Perfs:

Top	Bot	Thru	Comments
4547	4550		
4509	4514		
4493	4499		

INVOICED
DEC 15 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: TBG

District: 01

Signed Michael Maier
SM (TECHNICIAN)

RECEIVED
OCT 24 2017
KCC DODGE CITY