

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-23600-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 30-16S-21W  
2968 feet from S Section Line, 4955 feet from E Section Line  
Lease Name: SUNLEY Well #: 2  
County: NESS Total Vertical Depth: 4375 feet

Operator License No.: 31086  
Op Name: RICHLAN DRILLING, A GENERAL PAR  
Address: 598 2ND AVE  
BEAVER, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 2 SX CMT
DVT	5.5	1632	0	WITH 165 SX CMT
PROD	5.5	4374	0	WITH 100 SX CMT
SURF	8.625	259		WITH 165 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/03/2017 8:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: RICK SCHREIBER Company: RICHLAN DRILLING Phone: (620) 587-3224

Proposed Plugging Method: SET CIBP TO BOTTOM WITH 2 SX CMT. RUN TBG TO 1650' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & FILL WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/03/2017 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4150' WITH 2 SX CMT. RUN TBG TO 1650' & PUMPED 200 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4368	4370	CSG	

INVOICE  
11/15/2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED  
NOV - 8 2017  
KCC DODGE CITY

Signed

*Michael Maier*

(TECHNICIAN)

TA