

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-23380-00-00  
Spot: N2SESENE Sec/Twnshp/Rge: 7-9S-24W  
2250 feet from N Section Line, 330 feet from E Section Line  
Lease Name: BEAN Well #: 1-7  
County: GRAHAM Total Vertical Depth: 4071 feet

Operator License No.: 6861  
Op Name: RON'S OIL OPERATIONS INC  
Address: 1889 200TH AVE  
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4064		175 SX
SURF	8.625	220		200 SX
T1	2.375	3970		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2017 10:00 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: TERRY GARRISON Company: RON'S OIL OPERATIONS INC DBA Phone: (785) 421-3640

Proposed Plugging Method: Ordered 300 sx 60/30 pozmix 4% gel cement, 15 sx gel and 400 # hulls.  
Perforations: 3958' - 3964' and 4002' - 4004'.  
DV Tool at 2180' w/500 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/01/2017 12:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto casing and pumped 65 sx cement w/300 # hulls followed by 13 sx gel. Then followed with 220 sx cement. Shut in pressure 400 psi. Tied onto backside and squeezed with 10 sx cement. Shut in pressure 300 psi.

GPS: 39.28522 -100.03443

Perfs:

Top	Bot	Thru	Comments
4002	4004		
3958	3964		

Remarks: SCHIPPERS CEMENT TICKET # 609

Plugged through: CSG

District: 04

Received  
KANSAS CORPORATION COMMISSION

Signed \_\_\_\_\_

(TECHNICIAN)

CM

NOV 06 2017

NOV 20 2017  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

INVOICED

DEC 15 2017