

STATE OF KANSAS
STATE CORPORATION COMMISSION
10 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24,379-0000

LEASE NAME Bitter "D"

WELL NUMBER 1-8

1800 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 8 TWP. 16S RGE. 13W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 11-18-97

Plugging Completed 11-19-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd. St. North #300 Wichita, Ks. 67226

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3450'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each section.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	426'	None
				5-1/2"	3447'	1600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each section.
Dumped 5 sacks cement on top of CIBP. Shot @2400' and 1600'. Pumped 124 sks. cement @1600', w/150# hulls, pulled to 1025', pumped 40 sks. cement and 150# hulls, pulled to 1025'; pumped 40 sks. cement and 150# hulls, pulled to 500', pumped 35 sks. cement w/100# hulls, pulled to 150' and circulated 35 sks. cement to surface. 60/40 Pos, 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 3rd. day of December, 19 97

[Signature]
Notary Public

My Commission Expires: _____

