

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Barton County, Sec. 8 Twp. 16 Rge. 13W(E) (W)

Location as "NE/CNW%SW%" or footage from lines NW/NW/NW

Lease Owner T.C. Johnson Estate

Lease Name Bitter Well No. #8

Office Address 705 Fourth National Bank Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_\_\_

Application for plugging filed Yes 19\_\_\_\_

Application for plugging approved Yes 19\_\_\_\_

Plugging commenced \_\_\_\_\_ 8-17 19 59

Plugging completed \_\_\_\_\_ 8-24 19 59

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Donald Truan

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3353 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	32# surface	
				7" L.W.	Casing	1,635'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Measured into T.D. 3353 1/2'.  
Plugging started 8-17-59. Finished 8-24-59.  
Plugged off bottom with 10 ft. rock bridge and dumped 5 sacks of cement. Worked and shot pipe. Shot 7" casing at 1,635'.  
Layed down pipe and squeezed well as follows: Mixed in 15 sacks of mud, followed with 40 sacks of cement. Mixed 10 sacks of cement for cap on well. Well completed.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 2 1959

CONSERVATION DIVISION  
Wichita, Kansas

9-2-1959

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.  
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J.O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes  
Box 221, Great Bend, Kans  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1959

My commission expires November 8, 1960.  
Letty S. Edman Notary Public.

PLUGGING  
FILE SEC. 8 T. 16 R. 13W  
BOOK PAGE 61 LINE 15


T. C. JOHNSON  
 Henry Bitter Jr. No. 8.

SEC. 8 T. 16 R. 13W  
 NWE 1/4

15009-03486-0000

Total Depth. 3354'  
 Comm. 12-4-38 Comp. 12-31-38  
 Shot or Treated. 2000 Gals.  
 Contractor. Mitchell Drilg. Co.  
 Issued. 3-4-39

County. Barton



CASING:  
 10" 624'  
 7" 3346 1/2'

Elevation.

Production. Pot. 2319 B.

Figures Indicate Bottom of Formations.

surface hole	30
shale & lime	657
red rock, shal. shells	860
anhydrite	910
shale & shells	1178
shale	1210
salt	1400
shale & lime shells	1505
brkn lime	1685
shale	1693
shale & lime	1745
lime	1781
lime brkn	1895
lime	1960
shale	2020
lime	2120
shale & shells	2274
shale	2328
lime	2370
shale	2540
lime	2600
shale & shells	2680
shale	2725
lime	2990
lime brkn	3013
lime	3140
lime brkn	3147
3347=3346 1/2' SLN	
lime	3354
Total Depth.	