


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 31 Twp. 21S Rge. 8 (E) W (W)
Location as "NE/CNW/SW" or footage from lines W/2 E/2 NE
Lease Owner Hinkle Oil Company
Lease Name Yeakel Well No. 1
Office Address 1016 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 19, 1968 19
Application for plugging filed October 19, 1968 19
Application for plugging approved October 19, 1968 19
Plugging commenced 3:00 PM, October 19, 1968 19
Plugging completed 12:00 PM - Midnight - October 19, 19 68
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3462' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	252'	None
				5 1/2"	3461'	2479'
RECEIVED STATE CORPORATION COMMISSION OCT 25 1968 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 3050'. Mixed 75 cu. ft. cement and pumped down casing. Stopped cement plug at 3050'. Shot 5 1/2" pipe off at 2479'. Pulled, and laid down. Filled hole with heavy mud. Set Halliburton plug and hulls at 245'. Put 25 sacks cement thru drill pipe. Heavy mud up to 40'. Set plug and hulls at 40', 10 sacks of cement to the base of the cellar, 2 sacks of cement in rat hole. Pipe was pulled and hole plugged with rotary.

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sterling Drilling Company
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
Rollin Mead (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rollin Mead
STERLING DRILLING COMPANY
Rollin Mead, President
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of October, 19 68.

Bernard Laudermilk
Bernard Laudermilk, Notary Public.

My commission expires _____
BERNARD LAUDERMILK, Notary Public
Commission Expires January 22, 1970

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- YEAKEL #1
LOCATED: NW SE NE, Section 31-21S-8W, Rice County, Kansas

OWNER: HINKLE OIL COMPANY
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 27, 1968
COMPLETED: October 4, 1968

TOTAL DEPTH: 3460'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 60	Sand	Ran 6 Joints 8 5/8" New Casing. Pipe set at 252' Kelly Bushing - Pipe Tally 243 - 18'. Cemented with 260 sacks Pozmix NA5 cement. Plug down at 5:15 PM, 9-27-68.
60 - 252	Shale and Shells	
252 - 685	Shale	
685 - 1330	Shale and Shells	
1330 - 2790	Lime and Shale	
2790 - 3386	Lime	
3388 - 3400	Shale and Miss.	
3400 - 3420	Lime	Ran 82 joints 5 1/2" used 11# Range 3 Casing. Set at 3459' with 150 sacks cement by Halliburton. Plug down at 10:00 AM, 10-4-68.
3420 - 3460	Miss. Lime and Shale	

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1968
CONSERVATION DIVISION
Wichita, Kansas