

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

Rice County. Sec. 15 Twp. 21S Rge. (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines N 1/2 NE 1/4 NE 1/4

Lease Owner Adair Oil Company

Lease Name Ross-Hurley Well No. 1

Office Address Box 7011, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-2 19 70

Application for plugging filed 10-2 19 70

Application for plugging approved 10-2 19 70

Plugging commenced 10-2 19 70

Plugging completed 10-3 19 70

Reason for abandonment of well or producing formation No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production ---- 19 --

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas

Producing formation Depth to top Bottom Total Depth of Well 2967 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	218'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set first plug at 450 feet with 40 sacks;  
second plug at 200 feet with 20 sacks; top  
plug at 40 feet with 10 sacks, solid bridge  
to surface. Plugging completed 1:00 a.m. 10-3-70

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rains & Williamson Oil Co., Inc.  
Address 1425 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wilson Rains (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains Wilson Rains  
1425 Wichita Plaza, Wichita, Kansas (Address)

Subscribed and sworn to before me this 6 day of October, 19 70  
Jeanine Durand Notary Public.  
March 31, 1974



## ROTARY DRILLING LOG

Operator: Adair Oil Company  
 ROSS-HURLEY #1  
 N $\frac{1}{2}$ NE $\frac{1}{2}$ NE $\frac{1}{2}$  Sec. 15-21S-9W  
 Rice County, Kansas

Contractor: Rains & Williamson  
 Oil Co., Inc.  
 Commenced: 9-29-70  
 Completed: 10-3-70  
 Casing: 8-5/8"/218'/275 sacks


Formations

Sand and Shale	218'
Shale and Shells	700'
Shale	1100'
Shale and Shells	1328'
Shale	1640'
Lime and Shale	1975'
Shale and Lime	2720'
Lime and Shale	2925'
Lime	2967'
 Rotary Total Depth	 2967'


RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 13 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

We certify the above log is true  
 and correct, to the best of our  
 knowledge and belief.

RAINS & WILLIAMSON OIL CO., INC.

  
 Wilson Rains

Subscribed and sworn to me, a Notary Public within and for the State of  
 Kansas, County of Sedgwick, this 6 day of October, 1970.

  
 Jeanine Durand Notary Public



My Commission Expires: 3-31-74

ADAIR OIL COMPANY  
P. O. Box 7011  
Wichita, Kansas

15.159.20331.0000

October 5, 1970

Adair Oil Company, et al.  
Ross-Hurley #1  
N/2-NE-NE  
Section 15-21-9W  
Rice County, Kansas  
E1. 1674 K.B.

Comm: 9-28-70  
Comp: 10-2-70  
Contractor: Rains & Williamson  
8 5/8 @ 218 w/275 SX  
Pro: D & A

Figures indicate bottom of formations:

shale & lime	2476
lime	2769
shale	2774
lime	2802
shale	2905
lime	2912
shale & lime	2939
lime	2967
T.D.	2967

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Sample tops:

TOPEKA	2476	(-802)
HEEBNER	2769	(-1095)
DOUGLAS	2802	(-1128)
BROWN LIME	2905	(-1231)
LANSING	2939	(-1265)
T.D.	2967	

*Sherrill Compton*  
Sherrill Compton  
Geologist