

15-097-19036-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kiowa SEC. 2 TWP. 28S RGE. 19 E/W
Location as in quarters or footage from lines:

		2	
	X		

Locate Well
correctly on above
Section Platt.

Lease Owner TGT Petroleum Corp.
 Lease Name Pyle A Well No. 1
 Office Address 209 E. William, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Core Hole
 Date Well Completed 4/3/82
 Application for plugging filed _____
 Plugging commenced 10:30 AM 4/6/82
 Plugging completed 12:41 PM 4/6/82
 Reason for abandonment of well or producing formation Finish logging

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
 Producing formation _____ Depth to top _____ bottom _____ T.D. 1280
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				5 1/2"	217	Surface (cemented)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Halliburton hookup onto 5 1/2" surface, pump in 2 sacks gel, 2 sacks hulls on top of 40 visc. mud. Then pump 60 sacks Halliburton common 3% into casing, followed by 1/3 bbl. clear water to clear valve, swedge & landing nipple, shut in valve at 550 lbs. psi leaving cement plug in hole from 15' to 750'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

B. Lynn Herrington (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. Lynn Herrington
209 E. William-Wichita, Ks.
 (Address)

RECEIVED
 APR 21 1982
 CONSERVATION DIVISION
 WICHITA, KANSAS

AND SWORN TO before me this 20th day of April, 1982

Judith K. Moser Notary Public.

My Commission expires: 5/17/85

