


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County. Sec. 10 Twp. 21 Rge. 6 (E) (W)
Location as "NE/CNWxSWx" or footage from lines NW NE NW
Lease Owner H.C. Bennett
Lease Name Brown Brown Well No. 2
Office Address Drawer # 31, Augusta, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 28 19 48
Application for plugging filed July 10 19 56
Application for plugging approved July 10 19 56
Plugging commenced July 20 19 56
Plugging completed July 24 19 56
Reason for abandonment of well or producing formation
production exhausted
If a producing well is abandoned, date of last production September 19 55
Was production obtained from the Conservation Division or its agents before plugging was commenced? Yes
Ruel Durkee

Name of Conservation Agent who supervised plugging of this well

Producing formation Miss. Chert Depth to top 3420 Bottom 3436 Total Depth of Well 3436 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3418'	3122'
				8-5/8"	100'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back with gravel to 3410'. Dumped 6 sacks of cement. Shot pipe off at 3122'. Pulled pipe and mudded hole to 175'. Set rock bridge and dumped 25 sacks cement. Finished mudding hole and dumped 5 sacks of cement at base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address R. R. #4, Hutchinson, Kansas

STATE OF Kans., COUNTY OF Reno, ss.
Employee (employee of owner) or (manner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #4, Hutchinson, Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July, 19 56

My commission expires August 12, 1957

Bert Self
Notary Public.

PLUGGING
FILE SEC. 10 T. 21 R. 6 W.
BOOK PAGE 78 LINE 19

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1956

CONSERVATION DIVISION

8-20-1956