


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rice County. Sec. 4 Twp. 21S Rge. (E) 7 (W)  
Location as "NE/CNW/SW" or footage from lines SE SE  
Lease Owner Jayhawk Oil Co.  
Lease Name Thede Well No. 1  
Office Address 103 One Twenty Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 19 68  
Application for plugging filed November 27 19 68  
Application for plugging approved December 2 19 68  
Plugging commenced December 2 19 68  
Plugging completed December 6 19 68  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Tolman  
Producing formation Mississippi Depth to top Bottom Total Depth of Well 3397 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" |        | None       |
|           |         |      |    | 5-1/2" | 3384'  | 2937.85    |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

5 1/2' @ 3384' w/75 sacks.  
Sanded hole from 3397 to 3375' - 5 sacks cement.  
Shot pipe @ 2907'.  
Pulled 90 jts (2937.85') 5 1/2' casing.  
Mudded hole to 210'.  
Rock bridge 210' to 200'.  
25 sacks cement @ 200'.  
Rock bridge 40-30'.  
10 sacks cement to surface.  
Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Braden-Deem, Inc.  
Address 210 One Twenty Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*  
210 One Twenty Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of December, 1968

My commission expires March 21, 1970  
*[Signature]* Notary Public.

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- THEEDE #1  
LOCATED: SE SE Section 4-21S-7W, Rice County, Kansas.

OWNER: Jayhawk Oil Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 6-26-68  
COMPLETED: 6-30-68

TOARTY TOTAL DEPTH: 3385'

| <u>LOG</u> |                       | <u>CASING RECORD</u>   |
|------------|-----------------------|--|
| 0 -        | 66 Sand               | Ran 4 joints 8 5/8", 162'. Cemented @ 175' K.B. with 190 sacks common cement, 2% gel. Plug down at 3:00 PM, 6-26-68.         |
| 66 -       | 175 Red Bed and Shale |  |
| 175 -      | 1000 Shale            |  |
| 1000 -     | 3318 Lime and Shale   |  |
| 3318 -     | 3380 Lime             |  |
| 3380 -     | 3385 Chert            | Ran 105 joints 5 1/2 OD to 3392'. Cemented @ 3384' with 75 sacks 50/50 Pozmix salt saturated. Plug down @ 11:30 PM, 6-30-68. |

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas