

CONTRACTOR'S WELL LOG

Operator Carl Lebsack Farm Name Miller No. #1
 Location N¹/₂ of the SW¹/₄ of Sec. 8 TWP 21 South, Rge ¹⁰ ~~22~~-W, Rice County
 Pool Name _____ County Rice State Kansas
 Commencement Date 5-22-49 Completion Date 6-6-49

LOG OF WELL

* All measurements from top of rotary bushing

Depth		Formation	Deviation		Remarks.
From	To		From	Vertical	
0	85	Sand gravel			
85	194	Red Bed (A Iron)	1/2°	180'	
194	420	" "			
420	440	Anhydrite			
440	620	Gray Bed	1/4°	500'	
620	705	Baba-Shells			
705	740	Salt Top			
740	970	Shale-Lime-Shells	1/2°	1000'	
970	1260	" -Shells			
1260	1355	Lime-Shale			
1355	1490	Fort Riley Lime			
1490	1585	Lime-Shale			
1585	1625	Lime			
1625	1650	Sandy Lime	1/8°	1500'	
1650	1660	Lime			
1660	1715	Lime-Shale			
1715	1830	Lime			
1830	1900	Lime-Shale			
1900	1985	Lime			
1985	2036	Shale-Shells			
2036	2050	White Lime			
2050	2090	Lime			
2090	2160	Shale			
2160	2180	Lime	1/8°	2045'	
2180	2280	Shale-Shells.			
2280	2355	Lime-Shale			
2355	2390	Lime			
2390	2440	Lime-Shale			
2440	2495	Shale			
2495	2549	Lime	3/4°	2499'	
2549	2555	Gumbo-Shale			
2555	2602	Blue Sand			
2602	2640	White Lime			
2640	2793	Lime			
2793	2823	White Sand			
2823	2870	Lime			
2870	2892	Lime-Shale			
2892	2896	Heebner Shale			
2896	2995	Lime-Shale			
2995	3328	Lime	1 1/8°	3000'	
3328	3355	Conq.			
3355	3359	Brown Chartz Lime.			
3359	3402	Shale			
3402	3430	Arbuckle Total Depth.			

PLUGGING
 FILE SEC 8 T-21 R 104
 BOOK PAGE 100 LINE 24

Casing Left in Hole after Completion.

Set 194' (10 jts) 8-5/8" casing.
 Plugged at Total Depth 3430'

State of Kansas } SS
 County of Rice }

The undersigned certifies that to the best of his knowledge and belief the above facts are true and correct.

RECEIVED
 Conservation Div.
 JUL 30 1949

STATE OF KANSAS
 COMMERCIAL CORPORATION
 Notary Public
 Stag Drilling Inc. Pres.

Subscribed and sworn to before me this 13th day of June, 1949.

My commission expires
 March, 1, 1951

Orlando Miller
 Notary Public.