

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Rice County. Sec. 5 Twp. 21. Rge. 7W (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines E/2 NW

Lease Owner Simon Lebow

Lease Name Walter J. Oden Well No. 3

Office Address 807 Palace Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed February 12, 1947 19

Application for plugging approved February 14, 1947 19

Plugging commenced March 24, 1947 19

Plugging completed March 24, 1947 19

Reason for abandonment of well or producing formation

unproductive

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, McPherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 6 sacks of cement at 3324. Shot pipe off at 2450'.
Pulled pipe, mudded hole to 150'. Put 30 sacks of cement at 150'.
Finished mudding hole and put 8 sacks of cement at top of surface pipe.

APR 26 1947

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Simon Lebow
Address 807 Palace Bldg.
Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Simon Lebow (employee or owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Simon Lebow
Simon Lebow, Individual

(Address)

SUBSCRIBED AND SWORN to before me this 25th day of April, 1947

H. J. Sanders
Notary Public.


My commission expires May 19, 194

H.B.GARDEN.
 Oden No. 3

SEC. 5 T. 21 R. 7W.
 CEL NW

Total Depth, 3367 P.B. 3361
 Comm. 4-2-41 Comp. 4-28-41
 Shot or Treated.
 Contractor, H.B.Garden.
 Issued. 6-28-41

County Rice.



CASING.
 13" 50'
 7" 3329'

Elevation.

Production. Pot. 96 B.

Figures Indicate Bottom of Formations.

red bed	73	
shale red & green	325	
red bed and blue shale	675	
salt	930	
shale & gyp	970	
shale & shells	1090	
shale and lime shells	1205	
lime shale and gyp	1275	
shale and lime shells	1350	
lime and shale	1415	
broken lime	1430	
shale and lime	1470	
shale and shells	1570	
broken lime	1655	
limo and shale	1965	
shale	2065	
shale and limo shells	2155	
lime and shale	2240	
shale	2285	
limo	2367	
shale	2390	
broken limo	2448	
limo	2745	
shale and shells	2835	
shale	2925	
limo	3220	soft 2993-3009
broken limo	3225	
shale and shells	3313	
broken limo and chert	3324	
shale	3326	
red bed	3328	
conglomerate and red shale	3339	
1st show of gas conglomerate	3367	
Total Depth.		
P.B. 3361		

MAR 29 1947

Top of Conglomerate 3329

PLUGGING
 FILE SEC 5 T21 R7W
 BOOK PAGE 97 LINE 42

This plugging record should complete
the file for your records on our

Plugging Walter J. Oden #3.

SIMON LEBOW